


## जलकल विभाग, नगर निगम, गोरखपुर

कार्य का नाम : वार्ड सं० 55 अलहदादपुर मुख्य मार्ग से अमीन गली में मनोज श्रीवास्तव के मकान तक 90 मीटर 160एमएम पीवीसी पाइप डालकर सीवर लाइन विस्तार का कार्य।

### बिल आफ क्वान्टिटी

क्रमांक	कार्य का विवरण	मात्रा	दर
1.	Dismantling & Resoiling of cement brick self labour.	28 M <sup>3</sup>	
2.	Dismantling of C.C. road.	35 M <sup>3</sup>	
3.	Exavation in ordinary soil for the laying of sewer line including lift up 1.5 meter refilling work etc.	63 M <sup>3</sup>	
4.	Exavation for sewer chamber.	27 M <sup>3</sup>	
5.	160 mm sewer for laying.	90 mt.	
6.	S/O 160mm PVC pipe for sewer line.	90 mt.	
7.	P.C.C. 1:6:12 by brick ballast.	1.57 M <sup>3</sup>	
8.	C.C. in 1:2:4 by stone ballast.	2.36 M <sup>3</sup>	
9.	Ist class B/W in 1:3 fine cement & sand etc.	6.318 M <sup>3</sup>	
10.	12m thick cement plaster in 1:3 fine cement and sand etc.	19.76 M <sup>3</sup>	
11.	Laying of R.C.C. slab 1:2:4 by stone ballast.	0.336 M <sup>3</sup>	
12.	Reinforcement for total area item no. 11	0.395 Q	
13.	S/O man hole cover with angle iron with 10mm thick plate with cutting, velding etc.	7 nos.	
14.	Fixing of main hole cover with jointing.	7 nos.	
15.	Jointing of sewer line in main hole sewer Chamber.	7 nos.	
16.	Cleaning of site and disposal of malba.	7 nos.	

ठेकेदार/फर्म का हस्ताक्षर एवं सील

  
 महाप्रबन्धक (जलकल)  
