

कार्यालय : जलकल विभाग, नगर निगम, गोरखपुर।

निविदा दिनांक 28.12.2021

आगणन धनराशि रू0 2,24,951/-

निविदा फार्म मूल्य रू0 250/-

घरोहर धनराशि रू0 22,500/-

कार्य का नाम : वार्ड सं0 21 बेतियाहाता आवास विकास कालोनी में डा0 बग्गा व डा0 कविता दूबे के आवास के पास डीप सीवर चैम्बर का निर्माण कार्य।

फर्म का नाम व पता

रसीद सं0

दिनांक

बिल आफ क्वान्टिटी

क्र0सं0	कार्य का विवरण	मात्रा	दर
1.	Patch Road cutting	9 m ²	
2.	Patch Road cutting	9 m ²	
3.	Kharnja Road cutting	9 m ²	
4.	Excavation w/crudy Soil for benches	49.5 m ³	
5.	cc w/10:16:32 By Brick Ballast	1.8 m ³	
6.	cc w/12:4 By Stone Ballast	1.35 m ³	
7.	1st class By 10 w/1:2 for Land 2 Down	18.504 m ³	
8.	200 mm thick cement plaster	52 m ²	
9.	RCC slab w/1:2:4 By Stone Ballast	1.621 m ³	
10.	Reinforcement w/ RCC slab	1.900	
11.	wooden shuttering	10 NOS	
12.	verticaling	10 Nos	
13.	Sp foot 2.21	16 Nos	
14.	Cutting of Sewer chamber	1 NOS	
15.	Supply of man hole cover	4 NOS	
16.	fixing of man hole cover	4 NOS	

Sharma
अक्षर अभियन्ता (जल)

Sharma
सहायक अभियन्ता (जल)

Earnest Money:-

Attach.....Yes/No

FDR/CDR/NSC.....

Rate.....Below/Above in Word.....

Cutting/Over Writing.....Yes/No

हस्ताक्षर

फर्म/टेकेंदार का नाम व पता

कार्यालय : जलकल विभाग, नगर निगम, गोरखपुर।

निविदा दिनांक 28.12.2021

निविदा फार्म मूल्य रू० 660/-

आगणन धनराशि 6,61,482/-

घरोहर धनराशि रू० 68,200/-

कार्य का नाम : वार्ड सं० 01 महादेव झारखण्डी टुकड़ा नं० 1 भैरोपुर काली मन्दिर नलकूप से अनुमान मन्दिर चौराहे तक 140 मी० (एमएस) 150 एमएम पाइप लाइन विस्तार कार्य।

फर्म का नाम व पता.....

रसीद सं०...../.....

दिनांक.....

बिल आफ क्वान्टिटी

क्र०सं०	कार्य का विवरण	मात्रा	दर
1	Water locking Road cutting Complete labour	63 m ²	
2	Patch Road cutting with Complete labour	35 m ²	
3	Excavation underlay Soil for trenches	98 m ³	
4	Laying of ms. Pipe 150 mm	140 m	
5	Supply of ms. D.P Pipe 150 mm 3 m length	46 Nos	
6	Supply of ms. Tail piece 150 mm	2 Nos	
7	Supply of ms. Tee 150 mm	1 Nos	
8	Supply of ms. Elbow D.P 150 mm	4 Nos	
9	Supply of rubber packing sheet	40 kg	
10	Supply of Neel Balts	60 kg	
11	Supply of C.I.D. Joints	2 Nos	
12	Tee connection 150x150 mm Complete	01 Job	
13	Joint connection 150x150 mm Complete	01 Job	

Sumit
14/12/21
अवर अभियन्ता (जल)

Sumit
15-12-2021
सहायक अभियन्ता (जल)

Earnest Money:-

Attach.....Yes/No

FDR/CDR/NSC.....

Rate.....Below/Above in Word.....

Cutting/Over Writing.....Yes/No

हस्ताक्षर.....

फर्म/ठेकेदार का नाम व पता.....